



Causeway
P. O. Box 13
Port Alfred 6170

NDLAMBE MUNICIPALITY

(046) – 624 1140
(046) – 624 2669
portalfred@ndlambe.co.za



Please address all correspondence to the Municipal Manager

20 August 2020

To: ALL TENDERERS

Dear All

ADDENDUM NUMBER 1: CONTRACT NUMBER: 127/2020uj(WSIG2020-003): UPGRADE OF SEWER PIPELINE IN CARNATION STREET (STATIONHILL)

The above subject matter bears reference with the clarification meeting that was held on the **17th of August 2020** at **11h00** and clarity questions by tenderers.

Herewith please find Addendum No. 1 with respect to the abovementioned tender. Please note that tenderers have responsibility to ensure all the changes are incorporated into the tender documents.

1. Details of the addendum

Tenderers are to note the following changes in their tender:

T2.3 Adjudication of tenders for scoring Page 1 under General conditions:

Replace functionality breakdown as per the following:

The following functionality criterion is to be utilized. A minimum threshold obtaining a total score of 70 points and above will be evaluated in terms of price and B-BBEE.

Criteria 2: Tenderers Expertise and Resources		30
2.2 Relevant Experience		
2.2.1 Completed sewer reticulation/bulk pipeline (Provide completion certificate and assessment form with signature of client)		20
2.2.1 Completed water reticulation/bulk pipeline (Provide completion certificate and assessment form with signature of client)		10

C.2 Bill of Quantities Page 1 item 4 Excavations
Add item 4.2 Excavation in Hard rock as follows:

ITEM	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
4.2	Hard rock excavation	m ³			Rate Only

Also see the attached revised bill of quantities including item 4.2 as indicated above.

Please do not hesitate to contact us should you require additional information or clarification.

Yours Faithfully



N VITHI MASIZA
DIRECTOR - INFRASTRUCTURE

C2.2 Bill of Quantities

CONTRACTOR:					
CONTRACT NO: 127/2020(WSIG2020-003)					
PROJECT NAME: UPGRADE OF SEWER PIPELINE IN CARNATION STREET (STATION HILL)					
ITEM	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
	UPGRADE OF SEWER PIPELINE IN CARNATION STREET (STATION HILL)				
1	PROVISION AND GENERAL				
	1.1 Site Establishment	Sum	1		
	1.2 Security	Sum	1		
	1.3 Community Liason Officer	Sum	1		
2	HEALTH AND SAFETY COMPLIANCE				
2.1	Pe rsonal Protective Equipment	Sum	1		
2.2	Health and Safety File	Sum	1		
2.3	Medical Surveillance	Sum	1		
2.4	Safety Rep.	months	2		
3	CLEARING AND GRUBBING				
3.1	Clear vegetation and trees of girth up to 1 m	No	24		
3.2	Clear 2m wide strip form vegetation	m ²	720		
4	EXCAVATIONS				
	Excavate in all materials for trenches backfill, compact, and dispose of surplus/unsuitable material, shoring and dewatering for pipes up to & including 160mm dia. for total trench depth:				
4.1	Average Depth of 4m	m3	2 160		
4.2	Hard Rock excavation	m3			Rate Only
3.	BEDDING				
	Commercial Sources				
3.1	Selected bedding material from the commercial source.	m ³	260		

Contractor _____ Witness 1 _____ Witness 2 _____ Employer _____ Witness 1 _____ Witness 2 _____

5.	PIPEWORK				
	Supply, lay, joint ,backfill and test the following sewer pipes with flexible joints, incl. couplings & all specials:				
5.1	110mm diam., Class 34 solid wall	m	20		
5.2	160mm diam., Class 34 solid wall	m	400		
	Extra-over item 6.1.1 abd 6.1.2 for supply, lay, joint, bed Class B bedding and test the following specials:				
5.3	160mm x 110mm uPVC Y-Junctions	No.	8		
5.4	160mm end caps	No.	5		
6.	MANHOLES				
6.1	Over 2.5m up to 3.0m	No.	1		
6.2	Over 3.0m up to 3.5m	No.	1		
6.3	Over 3.5m up to 4.0m	No.	1		
6.4	Over 4.0m up to 4.5m	No.	1		
6.5	Over 4.5m up to 5.0m	No.	1		
6.6	Casting and building of manhole bases	No.	5		
6.7	Break into and connect to existing manhole including flexible joints as per Standard Details (See annexure E, Section C3.7) and make good all benching	No.	3		
7.	ERF CONNECTIONS				
	Supply and install erf connections to Standard Details as per complete, including extra excavation, formwork, joints, fittings, etc., for:				
7.1	Type 1	No.	1		
7.2	Type 2	No.	1		
7.3	Type 3	No.	1		
7.4	Type 4	No.	1		
7.5	Type 5	No.	1		
8	Name Boad	No.	1		
SUB – TOTAL					R -
VAT @ 15%					R -
TOTAL (Vat Inclusive)					R -

Contractor _____ Witness 1 _____ Witness 2 _____ Employer _____ Witness 1 _____ Witness 2 _____